

<b>Project:</b> Modular Housing, Sherborne			
<b>Status:</b>	<b>Ongoing</b> <input checked="" type="checkbox"/>	<b>Complete</b> <input type="checkbox"/>	<b>Other</b> <input type="checkbox"/>
<b>Summary:</b>	New housing development consisting of 14 modular homes and associated infrastructure.		
<b>Sector:</b>	Housing		
<b>Services:</b>	Foundations, drainage and roadways		
<b>Client:</b>	Fisher & Dean		
<b>Main Contractor:</b>	Fisher & Dean		
<b>Start Date:</b>	October 2021		
<b>Location:</b>	Sherborne, Dorset		
<b>Value:</b>	£500,000		
<b>Scope of Works:</b>	Reduce dig and stone up the road, install all main drainage throughout the site, then dig and pour all foundations, install services down through site and then the plot services, concrete all over sites with the specification of 50mm fall from middle to front and back, all plot drainage to be completed. The houses will be dropped and installed and once complete we return to finish off drainage such as the attenuation tanks for the storm drainage and complete all finishing's such as slabbing, kerbing the road and tarmac.		

