

| | | | |
|-------------------------|---|---|--|
| Project: | Modular Housing, Yeovil | | |
| Status: | Ongoing <input checked="" type="checkbox"/> | Complete <input type="checkbox"/> | Other <input type="checkbox"/> |
| Summary: | New housing development consisting of 8 modular homes and associated infrastructure | | |
| Sector: | Housing | | |
| Services: | Foundations, drainage and parking bays | | |
| Client: | Fisher & Dean | | |
| Main Contractor: | Fisher & Dean | | |
| Start Date: | June 2021 | | |
| Location: | Yeovil, Somerset | | |
| Value: | £400,000 | | |
| Scope of Works: | 8 plots for modular homes, a reduce dig was completed and then the site stoned for a piling mat as all 8 plots are piled. Once complete piles were dug around and a 50mm blinding added for the steel works. Once complete the foul and storm drainage was brought through the site as far as an attenuation tank. Water and the electric main were then laid down the footpath and installed to the water connections laid on phase 1. Parking bays were then stoned up with extra stone for the crane that will be on site to lift the houses into place. | | |

